

1	<u>DIVISION7.GR7</u>	Drainage Structures, Storm Sewers, Sanitary
2		Sewers, Water Mains, and Conduits
3		
4	<u>7-01.GR7</u>	Drains
5		
6	<u>7-01.SA1.GR7</u>	(Media Filter Drains)
7		(October 3, 2022)
8		Use in all projects with Media Filter Drains. Media Filter Drain
9		(MFD) is paid for by the SY and informational quantities
10		should be provided in the Contract. MFD Details in the plans
11		should show pay limits from the edge of shoulder to the catch
12		point. The items, Clearing and Grubbing and Seeding,
13		Fertilizing, and Mulching should be included as a separate
14		pay item. For additional information, refer the Highway
15		Runoff Manual.